

## NOTICE TO BIDDERS

Project No. S.A.P. 56-630-10

Sealed bids will be received until 1:00 P.M. February 17, 2010 by the County Auditor of Otter Tail County for Project No. S.A.P. 56-630-10; Lake Olaf Drawdown. Mailed bids should be sent to the County Auditor of Otter Tail County, 510 Fir Avenue West, Fergus Falls, Minnesota 56537. Hand carried bids should be delivered to the County Auditor of Otter Tail County, Otter Tail County Government Service Center, 500-600 Fir Avenue West, Fergus Falls, Minnesota.

S.A.P. 56-630-10 - From Lake Olaf North of 430<sup>th</sup> Street to 410<sup>th</sup> Street, in Sections 18, 19, 28, 29, 30 & 33 of Pelican Township, Northwest of Pelican Rapids

Approximate Total Length = 3.371 Miles

The Approximate Major Quantities of Work are as follows:

Mobilization - 1 L.S., Remove Pipe Culverts - 57 L.F., Salvage Fence - 220 L.F., Unclassified Excavation - 2,715 (P) C.Y., Salvaged Topsoil (EV) - 4,869 (P) C.Y., Aggregate Surfacing, Class 1 Modified - 108 Ton, Dozer - 10 Hour, Crawler Mounted Backhoe - 10 Hour, Granular Bedding (CV) - 42 (P) C.Y., Rock Bedding (CV) - 414 (P) C.Y., 57" Span CS Pipe-Arch Culvert - 57 L.F., 57" Span GS Pipe-Arch Apron - 1 Each, 30" RC Pipe Sewer - 716 L.F., Lift Station - 1 Each, 30" Steel Casing Pipe (Jacked) - 80 L.F., 24" HDPE Force Main - 9,750 L.F., 36" HDPE Pipe Sewer - 610 L.F., Construct Drainage Structure Design F - 1 Each, Construct Drainage Structure Design Special 1 - 1 Each, Construct Drainage Structure Design Special 2 - 1 Each, Construct Drainage Structure Design Special 3 - 4 Each, Construct Drainage Structure Design Special 4 - 1 Each, Random Riprap, Class II - 4 C.Y., Random Riprap, Class III - 22 C.Y., Fish Barrier - 1 L.S., Traffic Control - 1 L.S., Deciduous Tree 6' Ht B&B - 22 Tree, Silt Fence, Type Machine Sliced - 1,190 L.F., Temporary Rock Construction Entrance - 2 Each, Seeding - 1.18 (P) Acre, Seed Mixture 350 - 99 Pound, Mulch Material Type 1 - 1.3 Ton, Disk Anchoring - 0.65 (P) Acre, Erosion Control Blankets, Category 3 - 2,611 S.Y., Fertilizer Type 1 - 177 Pound, Rapid Stabilization Method 4 - 3,630 S.Y.

Minimum wage rates to be paid by the Contractors have been predetermined and are subject to the Work Hours Act of 1962, P.L. 87-581 and implementing regulations.

Bids will be opened and read publicly by the Otter Tail County Board of Commissioners or their designated representative, immediately after the hour set for receiving bids in the County Board Room at the Otter Tail County Government Services Center, 500-600 Fir Avenue West, Fergus Falls, Minnesota.

Proposals and Specifications may be examined and/or secured at the Office of the Otter Tail County Engineer, 505 South Court Street, Fergus Falls, MN 56537.

Cost of Proposal including plans is \$100.00 (Non-refundable).

Bids must be accompanied by a bidder's bond or certified check made payable to the County Treasurer, Otter Tail County, for at least five percent (5%) of the amount of the Proposal. Sealed bids shall be clearly marked "Project No. S.A.P. 56-630-10."

The County Board reserves the right to accept or reject any or all bids, portions, thereof, and to waive informalities.

Otter Tail County is an Equal Opportunity/Affirmative Action Employer.

---

Richard West, P.E., County Engineer  
Otter Tail County, Minnesota  
January 8, 2010